

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 8 Twp. 21 Rge. (E) 22 (W)

Location as "NE/CNW%SW%" or footage from lines C SE NE

Lease Owner Pickrell Drilling Company

Lease Name Tricker Well No. 3 SWD

Office Address 705 Fourth National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed March 25, 19 61

Application for plugging filed July 26, 19 66

Application for plugging approved July 27, 19 66


Plugging commenced October 20, 19 66

Plugging completed October 20, 19 66

Reason for abandonment of well or producing formation SWDW replaced with deeper SWDW

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well E. Eves, Box "F", Sublette, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1080 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PIT IN	PULLED OUT
				4 1/2"	1071'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mixed and pumped 4 sacks gel, 3 sacks hulls and

50 sacks cement. Cut off 4 1/2" @ bottom of cellar

Top of cement @ bottom of cellar.

1700
STATE CORPORATION COMMISSION
WICHITA, KANSAS
DEC 29 1966

CONSERVATION DIVISION
WICHITA, KANSAS

12-29-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY

Address 704 Fourth National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

C. W. Sebits
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of October, 1966

My commission expires May 10, 1970



L. M. Whiting
L. M. Whiting Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Bldg.
 Wichita, Kansas
 Rotary Drilling Commenced 3-2-61
 Rotary Drilling Completed 3-5-61

LOCATION: Tricker No. 3 - SWD
 C SE/4 NE/4 Section 8-21S-22W
 Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: 4½" 9.5# J-55 casing set @ 1071' and cemented with 150 sacks cement.
 Cement circulated to surface.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Sand & Shale	0 to 250'
Lime	250' to 280'
Shale & Sand	280' to 520'
Sand (Cheyenne)	520' to 540'
Red Shale (Permian)	540 to 765'
Anhydrite (Blaine)	765' to 780'
Shale	780' to 860'
Sand (Cedar Hills)	860' to 1049'
Shale	1049' to 1071'
RTD	1071'

RECEIVED
 STATE CORPORATION COMMISSION

DEC 29 1966

CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By *C. W. Sebitts*
 C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 28th day of December, 19 66, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared G. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

L. M. Whiting
 L. M. Whiting, Notary Public