

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-083-10208-0000

LEASE NAME Tricker

WELL NUMBER 2

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 8 TWP. 21S RGE. 22W (E) or (W)

COUNTY Hodgeman

Date Well Completed 11-11-60

Plugging Commenced 9-18-87

Plugging Completed 9-18-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company, Inc.

ADDRESS 110 North Market, Suite 205, Wichita, KS 67202

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well T.A.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-4-87 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Miss Depth to Top 4386 Bottom T.D. 4387

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Miss	Oil & Water	0	250	8 5/8"	250'	-0-
Cherokee	Oil & Water	0	4386	5 1/2"	4386'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

SEE BACK OF FORM.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. N/A

Address Box 31, Russell, Kansas 67665

STATE OF Kansas COUNTY OF Russell, ss.

Jack Gurley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says That he have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct.

(Signature) Jack Gurley

(Address) Jack Gurley, 110 N. Market, Suite 205  
Wichita, Kansas 67202

Subscribed and sworn to before me this 5th day of November, 19 87



NOV 6 1987

11-6-87

Wichita, Kansas

Beth Harmon  
Notary Public

My Commission Expires: 6-29-88 Beth Harmon

7

Description of plugging method:

Pumped down 5 1/2" casing; 1 sx hulls, 120 sx Allied ATL cement, 5 1/2" wiper plug, 20.4 bbls SW. Max P 600#. SIP 200#. Waited 2 days. Perforated 777-780 (base of Blaine). Pumped 50 sx common plus 75 sx 60/40 poz. Max P 500#, SIP 200#. FINAL STATUS: ATL Cement 4251'-835', Common and 60/40 poz 777-Surface. Could not pump into 8 5/8" x 5 1/2" annulus with 300#.

STATE OF TEXAS  
COUNTY OF HARRIS  
CORPUS CHRISTI