


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 16 Twp. 21S Rge. 22 (E) (W)

Location as "NE/CNW%SW%" or footage from lines Center of NW SE
Lease Owner Pickrell Drilling Company
Lease Name Weiland Well No. B-2
Office Address Wichita 2, Kansas, 705 Fourth National Bank Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed September 16, 1965
Application for plugging filed August 27, 1965
Application for plugging approved August 28, 1965
Plugging commenced September 4, 1965
Plugging completed September 16, 1965
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4365 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	270	NONE
				5 1/2"	NONE	2530'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in Rigged up, Dug out cellar

Working Pipe

Working Pipe

Shot Pipe @ 3800', Spotted Oil

Working Pipe & Shooting

Pulling Pipe

Pulling Pipe

Pumping 25 sx. Cement @ 700', 25 sx. Cement @ 300', Cap Well with 15 sx. Cement

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. O. Forbes*
P. O. Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of September, 1965

My commission expires September 16, 1965
May 27, 1969

Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita 2, Kansas

Rotary Drilling Commenced 8/15/61

Rotary Drilling Completed 8/27/61

LOCATION: WIELAND B #2 - C NW SE, Sec. 16-21S-22W,
Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 272' (6 jts.) 8 5/8" 20# surface casing w/155 sacks cement. Circulated.
4355' (141 jts.) 5 1/2" 14# Smls Casing cemented w/100 sacks cement.
Completed 6:15 A. M. 8/27/61

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>Circulated for Samples</u>	
75'	Post Rock & Clay	4292'	
150'	Black Shale	4351'	
215'	Blue Shale	4360'	
340'	Shale	4365'	
365'	Shale & Sand		
590'	Shale		
		<u>Slope Test</u>	
800'	Red Bed & Shale	1435'	0°
830'	Shale & Shells	2625'	0°
895'	Red Bed	3535'	0°
1090'	Sand & Shale	4045'	0°
1435'	Red Bed & Shale		
1465'	Anahydrate		
		<u>S. L. M.</u>	
1900'	Shale & Shells	3693'	
2340'	Lime & Shale	3900'	
2695'	Lime	4292'	
3585'	Lime & Shale		
3725'	Sand, Lime & Shale		
3885'	Shale & Lime		
3975'	Lime		
4261'	Lime & Shale		
4292'	Ft. Scott		
4353'	Lime & Shale		
4357'	Mississippi Dolomite		
4365'	Mississippi Chert R.T.D.		

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1965

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 31st day of August, 1961, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson
Maxine Johnson Notary Public