


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 16 Twp. 21 Rge. (E)22 (W)
Location as "NE/CNW%SW%" or footage from lines SE SE SW
Lease Owner Pickrell Drilling Company
Lease Name Wieland "A" Well No. 1
Office Address 705 4th National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Sept. 19, 19 56
Application for plugging filed July 26, 19 66
Application for plugging approved July 27, 19 66
Plugging commenced October 20, 19 66
Plugging completed October 20, 19 66
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production November, 19 62
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eyes, Box "F", Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4550 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240	None
				5 1/2"	4484	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mixed and pumped 23 sacks gel, 3 sacks hulls and
60 sacks cement. Cut off 5 1/2" @ bottom of cellar.
Top of cement @ bottom of cellar.

12-29-66
RECORDED
CONSERVATION DIVISION
REC 29 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 4th Nat'l. Bank Bldg., Wichita, Kansas
(Address)


SUBSCRIBED AND SWORN to before me this 25th day of October, 19 66

My commission expires

May 10, 1970

L. M. Whiting
L. M. Whiting

Notary Public.



SE SE SW
SEC. 16-21S-22W
HODGEMAN COUNTY, KANSAS

F. G. WIELAND WELL NO. 1

CONTRACTOR: THE R. W. RINE DRILLING COMPANY

STARTED: AUGUST 16, 1956

COMPLETED: SEPTEMBER 8, 1956

LOG

SAND, ROCK & CLAY	0' - 240'	SYFO. @250' 3/4° 9-5/8" Csg. @240' w/150 sx.
BLUE CLAY, SHALE & SALT	240' - 603'	
SHALE, SAND & GYP	603' - 1425'	SYFO. @700' 1/2°, @1200' 1-1/2°
SHALE, ANHYDRITE & SAND	1425' - 1710'	SYFO. @1705' 1°
SHALE & ANHYDRITE	1710' - 2127'	
LIME & SHALE	2127' - 2370'	SYFO. @2240' 1°
SHALE, ANHYDRITE & SAND	2370' - 2434'	
LIME & SHALE	2434' - 3570'	SYFO. @2550' 3/4°, @2710' 3/4° SYFO. @2850' 3/4°, @3190' 3/4°, 3298' 3/4°.
LIME	3570' - 4211'	SYFO. @3450' 1/4°, @3565' 1/4° SYFO. @3735' 1°, @3970' 3/4°, @4095' 3/4°
LIME & SHALE	4211' - 4253'	SYFO. @4205' 1/2°
LIME	4253' - 4519'	SYFO. @4290' 1/2°, @4350' 1/2° SYFO. @4515' 1-1/2°
CHERT & LIME	4519' - 4550'	5-1/2" Csg. @4484' @/150 sx.
	T. D.	

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

I, R. M. GREEN, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE F. G. WIELAND WELL NO. 1, LOCATED SE SE SW, SECTION 16-21S-22W, HODGEMAN COUNTY, KANSAS.

R. M. Green
ASS'T. SECRETARY AND TREASURER

SUBSCRIBED TO AND SWORN BEFORE ME THIS 14TH DAY OF SEPTEMBER, 1956

John E. Egan
NOTARY PUBLIC

MY COMMISSION EXPIRES: 6/14/58

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1966
CONSERVATION DIVISION
Wichita, Kansas