


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 16 Twp. 21S Rge. (E) 22 (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE
Lease Owner Pickrell Drilling Company
Lease Name Wieland Well No. B-1
Office Address 2820 Paseo Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed September 24, 19 65
Application for plugging filed August 27, 19 65
Application for plugging approved August 28, 19 65
Plugging commenced September 4, 19 65
Plugging completed September 24, 1965 19 65
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott
Producing formation Depth to top Bottom Total Depth of Well 4399 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	420'	NONE
				4 1/2"	NONE	2491'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 450 feet to 45 feet for each plug set.

- 9-1-65 Moved in. Cleaned out cellar. Sanded to 4000', Dumped 10 sacks of cement
- 9/8/65 Shot Pipe @ 3800'
- 9/18/65 Cut off Casing clamps. Working pipe. Shot pipe @ 3000' & 2700'.
- 9/23/65 Shot pipe @ 2500'. Worked pipe. Pulling pipe.
- 9/24/65 Finished pulling pipe. Build rock bridge @ 450' with 35 sacks of cement. Build rock bridge @ 45' with 15 sacks of cement for cap.

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas-67530

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas-67530
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of September, 19 65

My commission expires May 27, 1968 Alice Ochs Notary Public.

PICKRELL DRILLING COMPANY
705 FOURTH NATIONAL BANK BLDG.
WICHITA 2, KANSAS

Memo to: Mr. S. S. Greider
State Corporation Commission of Kansas

Attached is a copy of the well log required to complete your file on the Wieland "B" No. 1 well which was plugged some time ago. You will notice from the well log that this well was drilled by Vandenbark and referred by them as the Wieland No. 2. When we bought the well we renamed it the Wieland "B" No. 1.

We wish to apologize in being late in furnishing you this well log as we had to obtain this copy from the Well Log Bureau.

PICKRELL DRILLING COMPANY

j1

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1966

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- VANDENBARK
Farm- Wieland No. 2

SEC. 16 T. 21 R. 22W
NW SW SE

Total Depth. 4634'
Comm. 9-19-58 Comp. 10-9-58
Shot or Treated.
Contractor. Barnett Drlg.
Issued. 3-28-59

County Hodgeman
KANSAS



Elevation. 2273' RB

Production. Dry

CASING:

8 5/8" 420' cem w/275 sx.

Figures Indicate Bottom of Formations.

shale & shells	315
sand	325
shale & shells	730
shale	850
sand	1080
shale	1210
shale & shells	1430
Anhydrite	1465
shale & shells	2180
shale & lime	2310
lime	2570
shale & lime	2675
lime	2765
lime & shale	2950
lime	3045
lime & shale	3285
lime	3360
lime & shale	3450
lime	3600
lime & shale	3715
lime	4619
sand	4627
lime	4634
Total Depth	

TOPS: SCOUT	
Lansing	3784
Mississippi	4354
Viola	4506

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1966
CONSERVATION DIVISION
Wichita, Kansas