

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

X			

Locate well correctly on above  
Section Plat

Hodgeman County. Sec. 16 Twp. 21 Rge. 22 (W) (W)  
 Location as "NE/CNW/SW" or footage from lines NW SW SE  
 Lease Owner James S. Vandebark  
 Lease Name Wieland Well No. 2  
 Office Address 826 Southeast Riverside Dr., Evansville 13, Indiana  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed October 9 19 58  
 Application for plugging filed October 9 19 58  
 Application for plugging approved October 9 19 58  
 Plugging commenced October 9 19 58  
 Plugging completed October 9 19 58  
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19       
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
 Producing formation - Depth to top - Bottom - Total Depth of Well 463 1/2 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.  
Filled hole from 463 1/2 feet to 400 feet. Set plug No. 1 at 410 feet, dumped 20 sacks of cement, filled hole to 40 feet. Set plug No. 2 at 40 feet with one-half sack hulls and 10 sacks cement on plug to fill bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.  
 Address 409 First National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick ss.  
Louise Burnett (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Louise Burnett Office-Manager  
409 First National Bank Bldg., Wichita, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 58

My commission expires February 27, 1960

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 14 1958  
 CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 16 T 21 R 22W  
 BOOK PAGE 136 LINE 12

BARNETT DRILLING, INC.  
LOG OF WIELAND WELL NO. 2  
NW SW SE, SECTION 16-21-22W  
HODGEMAN COUNTY, KANSAS

Commenced: 9-19-58

Completed: 10-9-58

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Shale & Shells	-0-	315	Set 8-5/8" Casing at 420 feet; cemented with 275 Sacks.
Sand	315	325	
Shale & Shells	325	730	
Shale	730	850	
Sand	850	1080	
Shale	1080	1210	
Shale & Shells	1210	1430	
Anhydrite	1430	1465	
Shale & Shells	1465	2180	
Shale & Lime	2180	2310	
Lime	2310	2570	
Shale & Lime	2570	2675	
Lime	2675	2765	
Lime & Shale	2765	2950	
Lime	2950	3045	
Lime & Shale	3045	3285	
Lime	3285	3360	
Lime & Shale	3360	3450	
Lime	3450	3600	
Lime & Shale	3600	3715	
Lime	3715	4619	
Sand	4619	4627	
Lime	4627	4634	Total Depth Dry and abandoned

CERTIFICATE

I, Louise Burnett, of Barnett Drilling, Inc. certify to the best of my knowledge and belief, that the foregoing is a true and correct log of the Wieland Well No. 2, located in the NW SW SE of Section 16-21-22W, Hodgeman County, Kansas.

Louise Burnett

Subscribed and sworn to by and before me in and for the County of Sedgwick, State of Kansas this 13th day of October, 1958.

Mildred F. Willis  
Notary Public

My commission expires February 27, 1960.

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 14 1958

<b>PLUGGING</b>			
FILE	SEC 16	T 21	R 22W
BOOK	PAGE 136		LINE 12

CONSERVATION DIVISION  
Wichita, Kansas