

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-185-00733-0000

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management Inc.

Complete Address: 1515 Wichita Plaza, Wichita, Kansas

Lease Name Glen Crissman Well No. # 1

Location NW SW SE Sec. 14 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4044

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 3:00PM Day 21st Month Feb. Year 1964

The Above well was plugged as follows:

201' of 8 5/8" surface pipe, cemented with 200 sacks. 3770' of 5 1/2" long
string, cemented with 200 sacks. Plug back to 3735'. Top perforation
3651'. Bottom of hole was sanded to 3640', and cemented with 5 sacks.
Hole was flowing with water and a squeeze job was necessary. 15 sacks
Gel-Mud and 80 sacks of cement was pumped into surface pipe, through an
8 5/8" swage, to a pressure of 150 lbs. Next morning swage was taken off,
and cement had coasted to 70' in the surface pipe. Hole was filled with
mud, and capped with 3 sacks cement. 2540' of 5 1/2" long string was recover-
ed from the hole.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED
DATE 2/27/64
INV. NO. 8675-W