

H
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1967
12-15-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beardmore Drilling Company

Complete Address: 700 One Twenty Bldg., Wichita, Kansas 67202

Lease Name Young Well No. A-1

Location C NE SE Sec. 16 Twp. 21 Rge. 21 ~~(N)~~ (W)

County Hodgeman Total Depth 4315'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Ralph Glenn & R.E. Smith

Address: 204 E. 6th. Ellinwood, Kansas License No. 396

Operation Completed: Hour 11:00AM Day 13 Month 12 Year 1967

The Above well was plugged as follows:

8 5/8" to 260' circulated w/ cement. 5 1/2" to 4310' cemented.

No perforations Plug bottom w/ sand & 5 sacks cement.

Top of cement 4270' Mud 4270' to 900'

Spotted 100 sacks cement 900' to 550' Mud 550' to 260'

Spotted 30 sacks cement 260' to 160' Mud 160' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Pulled 3280' of 5 1/2" casing. Halibuton Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

12/15/67

INV. NO.

6919-W

Signed:

Edmund Eves
Well Plugging Supervisor