

2

15.083-20031-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1967

11-28-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Beardmore Drilling Co.

Complete Address: 700-120 Bldg., Wichita, Kansas

Lease Name Mooney Well No. 2

Location SE NW Sec. 16 Twp. 21 Rge. 21 (X) (W)

County Hodgeman Total Depth 4360'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Rains & Williamson Oil Co.

Address: 1425 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 9:30AM Day 25 Month 11 Year 1967

The Above well was plugged as follows:

8 5/8" to 377' circulated w/ cement. Mud 4360' to 900'

Spotted 100 sacks cement 900' to 550' Mud 550' to 375'

Spotted 30 sacks cement 375' to 275' Mud 275' to 45'

Plug. Hulls & 15 sacks cement 45' to 0'.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward E. Lued
Well Plugging Supervisor

DATE 11-28-67

INV. NO. 6779-W