

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1972

CONSERVATION DIVISION
Wichita, Kansas

8-28-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Co.
Complete Address 705 4th Nat'l Bk Bldg., Wichita, Kansas
Lease Name Selfridge Well No. 1
Location C NW SE Sec. 8 Twp. 21 Rge. 22 ~~(E)~~ (W)
County Hodgeman Total Depth 4346'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated None
Plugging Contractor Russ Casing Pulling Co.
Address Great Bend, Kansas License No. 623
Operation Completed: Hour 11:00AM Day 21 Month 8 Year 1972

The above well was plugged as follows:

8 5/8" to 200' circulated w/ cement. 5 1/2" to 4339' cemented.
Top perforations 4002' Plug bottom w/ sand & 5 sacks cement.
Top of cement 3900' Mud 3900' to 380'
Spotted 30 sacks cement 380' to 280' Mud 280' to 200'
Spotted 30 sacks cement 200' to 100' Mud 100' to 45'
Plug, Hulls & 15 sacks cement 45' to 0'. Globe Cementing Pump Truck.
Pulled 387' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 8-30-72

INV. NO. 6238-W