

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Shirer Oil Company

Complete Address Box 118, Hoisington, Kansas

Lease Name Klinge Well No. 1

Location C SE SW Sec. 8 Twp. 21 Rge. 22 (E) (W)

County Hodgeman Total Depth 4426'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated None

Plugging Contractor Southwest casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:00PM Day 8 Month 6 Year 1973

The above well was plugged as follows:

8 5/8" to 279' circulated w/ cement. 5 1/2" to 4425' cemented.

Top perforations 4132' Plug bottom w/ sand & 5 sacks cement.

Top of cement. 4050' Mud 4050' to 800'

Spotted 80 sacks cement 800' to 500' Mud 500' to 270'

Spotted 30 sacks cement 270' to 170' Mud 170' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Allied Pump

Pulled 2350' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

DATE 6/12/73
INV. NO. 9494-W

Signed: Edgar J. Evers
Well Plugging Supervisor