


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Pawnee County. Sec. 9 Twp. 21 Rge. 20 (E) (W)  
Location as "NE/CNW/SW" or footage from lines C NE SW

Lease Owner Tom Palmer, Inc.  
Lease Name Fred W. Stommel Well No. 1  
Office Address 1330 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 8-19-65 19  
Application for plugging filed 8-19-65 19  
Application for plugging approved 8-19-65 19  
Plugging commenced 8-19-65 19  
Plugging completed 8-19-65 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4314 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	184'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 540' 20 sks. cement through drill pipe  
2nd plug @ 180' 20 sks. cement through drill pipe  
Mud to 30' 1/2 sk. bulls, plug 10 sks. cement

RECEIVED  
STATE CORPORATION COMMISSION

AUG 24 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite  
P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 1965

My commission expires October 19, 1968  
Notary Public.

DRILLER'S LOG

COMPANY: Tom Palmer, Inc.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: FRED W. STOMMEL #1  
 LOCATION: C NE SW Sec. 9-21S-20W  
 PAWNEE COUNTY, KANSAS  
 COMMENCED: 8-10-65  
 COMPLETED: 8-19-65

0	50	Soil, clay
50	115	Clay, sand
115	184	Redbed
184	425	Shale, sand
425	594	Redbed, shale
594	605	Anhydrite
605	700	Shale
700	885	Dakota Sand
885	1259	Red Shale
1259	1284	Anhydrite
1284	2120	Shale & Lime
2120	2310	Lime & Shale
2310	2870	Lime
2870	3238	Lime & Shale
3238	4235	Lime
4235	4240	Lime & Shale
4240	4314	Mississippi Lime
	<u>4314</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 24 1965  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" used surface casing @ 184' cemented with 175 sacks GL3.

I, Leslie Kite, do hereby certify that the above and fore-going is a true and correct copy of the log of the Fred W. Stommel #1 well, located C NE SW of Section 9, Township 21 South, Range 20 West, of Pawnee County, Kansas, as reflected by the records of Leben Drilling, Inc.

*Leslie Kite*

Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 23rd day of August, 1965.

*E. M. Benoit*

E. M. Benoit

My Commission Expires:  
 October 19, 1968