

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
State Required Affidavit
Mandatory Before Report to
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

Pawnee County, Sec. 11 Twp. 21, Rge. 20 (X) NW(W)
Location as "NE/CN/WSW" or lotage from lines C NW/4 NW/4
Lease Owner Melvin Bryant
Lease Name Bryant # 1 Well No. 1
Office Address 903 West 5, Larned, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 19 19 74
Application for plugging filed Yes June 19 19 74
Application for plugging approved June 19 19 74
Plugging commenced 12:45 A.M. June 19, 19 74
Plugging completed June 19 19 74
Reason for abandonment of well or producing formation Dry Hole

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Squeeze hole with 125 sacks common with 2% gel down the 8-5/8" casing

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1974

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Duke Drilling Company
Address Box 823, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON ss.
Leonard Williamson

(employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson

Box 823, Great Bend, Kansas
(Address)

Subscribed and Sworn to before me this 19th day of June 19 74

Bartholomew M. Hague
Notary Public.

My commission expires April 11, 1978

DRILLERS' WELL LOG

DATE COMMENCED: June 10, 1974
DATE COMPLETED: June 19, 1974

Melvin Bryant
Bryant # 1
C NW/4, NW/4
Sec. 11-T21-R20W
Pawnee County, Kansas

ELEVATION: 2142KB

0 - 620	Shale with sand streaks
620 - 630	Shells
630 - 720	Shale and Sand
720 - 950	Sand & Shale Streaks
950 - 1286	Red Bed
1286 - 1313	Anhydrite
1313 - 2060	Shale & Shells
2060 - 3647	Lime & Shale
3647 - 3653	Shale
3653 - 3702	Lime & Shale
3702 - 4055	Lime
4055 - 4197	Lime and Shale
4197 - 4219	Lime
4219 - 4276	Shale
4276 - 4300	Chert
4300	TD

FORMATION TOPS

ANHYDRITE	1286
HERRINER	3647
KANSAS CITY	3702
PAWNEE	4117
FT. SCOTT	4197
CHECROKEE	4219
MISSISSIPPI	4276
RTD	4300

SURFACE PIPE: Set used 8-5/8" surface casing, 28#, at 307' with 175 sacks common cement, 2% gel, 3% cc.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct the best of his knowledge.


Leonard Williamson

Subscribed and sworn to before me this 19th day of June, 1974.

MaCarthy M. Hague
Notary Public

April 11, 1978
My Comm. Expires

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1974
CONSERVATION DIVISION
Wichita, Kansas



FOUR RIVER
CANYON SKIN
25% COTTON