

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-083-20844-0000

API NUMBER 15-083-20, 844

LEASE NAME Lewis

WELL NUMBER 1-8

SPOT LOCATION NW SW

SEC. 8 TWP. 21 RGE. 21 (W)

COUNTY Hodgeman

Date Well Completed 8/31/81

Plugging Commenced 12/26/84

Plugging Completed 12/31/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR William E. Carl

ADDRESS 500 N. Water #800. CCNB Center North  
Corpus Christi, TX 78471

PHONE # (512) 888-4471 OPERATORS LICENSE NO. 5753

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? no If not, is well log attached? sent in with CP-1

Producing formation Mississippian Depth to top 4297 bottom 4389 T.D. 4389

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippian	oil & water	GL	465	8-5/8	465	0
		GL	4387	5-1/2	4387	950

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. sand to 4248', 5 sx on top. cut off casing at 950' and plugged as follows:  
2sx hulls, 10 sx gel, 60 sx 60/40, 10 sx gel, 2sx hulls  
125 sx 60/40 to fill surface. SIP 400 psi

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Ness County Well Service License No. 7527  
Address PO Box J Ness City, KS 67560

STATE OF Kansas COUNTY OF Ellis, ss: 1-15-85

Dennis Barry

agent (operator) of above-described well, being first duly sworn on oath, says: That

I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dennis Barry

(Address) Dennis Barry  
1117 Centennial  
Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 8th day of Jan, 1985



My Commission expires: 8-11-87

[Signature]  
Notary Public

DRILLERS LOG

#1-18 LEWIS  
 C NW SW Section 8-21S-21W  
 Hodgeman County, Kansas

OPERATOR: W. E. CARL  
 Suite 600, One Main Place  
 Wichita, Kansas 67202

CONTRACTOR: DUNNE-GARDNER PETROLEUM, INC.  
 Suite 250, 200 West Douglas  
 Wichita, Kansas 67202

COMMENCED: April 21, 1981

COMPLETED: April 29, 1981

CASING RECORD: 8-5/8" @ 465' w/325 sx  
 5-1/2" @ 4,387' w/ 125 sx


<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	320	Sand and Shells
320	475	Sand and Shale
475	665	Sand and Shells
665	757	Blaine
757	900	Dakota
900	2054	Sand and Shale
2054	3368	Shale and Lime
3368	3640	Lime
3640	4050	Shale and Lime
4050	4387	Lime
4387		Rotary total depth

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

Donald E. Hunt  
 Donald E. Hunt

Subscribed and sworn to before me this 30th day of April, 1981.



My appointment expires:  
 January 20, 1985

Kathleen L. Greger  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 14 1983

CONSERVATION DIVISION  
 Wichita, Kansas