

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-02-3-117

API NUMBER 15-145-21,440-0000

LEASE NAME Unruh

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Horizon Geophysical Corporation

SEC. 21 TWP. 21S RGE. 17W (E) or (W)

ADDRESS 3608 Clancy Lane El Paso, TX 79927

COUNTY Pawnee

PHONE#() OPERATORS LICENSE NO. 31777

Date Well Completed

Character of Well Oil

Plugging Commenced 2-7-97

(Oil, Gas, D&A, SYD, Input, Water Supply Well)

Plugging Completed 2-7-97

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 2469'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1117'	none
				5 1/2	2468'	1705'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 2400' & ran 5 sks cement. Shot at 2212', 2000', 1910', 1917', 1826', and 1705'. Finally worked pipe loose at 1705'. Pulled up to 1117' & pumped 50 sks cement. Pulled to 600' & pumped 25 sks cement. Pulled to 40' & pumped 10 sks cement. Pulled rest of pipe. Plugging complete. 60/40 poz 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Horizon Geophysical Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.



(Signature)

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of February, 1997

Notary Public

My Commission Expires:



Form 6
Revised 05-

3-3-97