

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 35 Twp. 21S Rge. (E) 17 (W)

Location as "NE/CNW%SW%" or footage from lines C S/2 SE SE

Lease Owner J. F. Darby Oil Co.

Lease Name State Hospital "A" Well No. 1

Office Address 1807 Philtower Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12/21/58 19

Application for plugging filed " 19

Application for plugging approved " 19


Plugging commenced " 19

Plugging completed " 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production Dry Hole 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation None Depth to top Bottom Total Depth of Well 3930 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	STATE PLUG IN	PULLED OUT
Heebner		3402		8-5/8		None
Lansing		3507				
Marmaton Lime		3780				
Arbuckle		3888				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud to 240 feet & set Wood Plug. Halliburton Oil Well Cementing Company pumped in 80 sacks of cement with one sack of Calcium Chloride filling inside of casing to top

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Co. Iron Drilling Co. Tools
Address

STATE OF Oklahoma COUNTY OF Tulsa ss.
J. L. Stackpole (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God

(Signature) J. L. Stackpole
Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 15th day of January, 19 59

B. Michal Notary Public.

My commission expires Feb. 28, 1960

PLUGGING
FILE SEC 35 T 21 R 17W
BOOK PAGE 9 LINE 5

DRILLING RECORD

Well No. 1 State Hospital "A"
 Located C S/2 SE SE
 Sec. 35-21S-17W
 Pawnee County, Kansas

Casing Record

1017' of 8-5/8" OD Surface
 pipe cemented w/ 450 sacks

No Oil String - Dry Hole

Well Commenced 12/5/58
 Drilling Commenced 12/5/58
 Drilling Completed 12/20/58
 Well Completed 12/21/58

WELL LOG

Surface Soil	0	-	30
Sand	30	-	35
Shale & Sand	35	-	130
Shale - Lime Streaks	130	-	410
Shale	410	-	445
Sand & Shale	445	-	585
Red Bed	585	-	1013
Anhydrite	1013	-	1045
Shale & Shells	1045	-	1535
Lime & Shale	1535	-	1640
Shale & Salt Strks	1640	-	1720
Lime	1720	-	1780
Shale & Shells	1780	-	1870
Lime & Shale	1870	-	1895
Lime	1895	-	2280
Shale & Lime	2280	-	2375
Lime	2375	-	2400
Shale & Lime Strks	2400	-	2515
Shale & Lime	2515	-	2980
Lime	2980	-	3035
Lime & Shale	3035	-	3233
Lime	3233	-	3370
Lime & Shale	3370	-	3512
Lime	3512	-	3780
Lime & Chalk	3780	-	3835
Lime	3835	-	3854
Cherty Conglomerate	3854	-	3865
Conglomerate	3865	-	3885
Conglomerate - Arbuckle	3885	-	3894
Lime	3894	-	3930 TD

C E R T I F I C A T I O N

State of Oklahoma)
 County of Tulsa) SS

I, J. L. Stackpole, employee of Iron Drilling Company, certify that the accompanying is a true and correct log of the above described well.

J. L. Stackpole

Subscribed to and sworn before me this 15th day of January 1959.

B. Muehl
 Notary Public

My commission expires Feb. 28, 1960

PLUGGING			
FILE	SEC 35	T. 21	R. 17W
BOOK	PAGE 9	LINE	5