


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County. Sec. 30 Twp. 21S Rge. 17W (E) (W)

Location as "NE/CNW/SWK" or footage from lines NW NW NE
Lease Owner K & E Drilling, Inc. and Cherokee Oil Company
Lease Name Gore Estate Well No. 1
Office Address 1006 Central Bldg., & 300 Schweiter Bldg., Wichita, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 1 19 54
Application for plugging filed June 1 19 54
Application for plugging approved June 1 19 54
Plugging commenced 8:00 a.m., June 1 19 54
Plugging completed 12:00 a.m., June 1 19 54
Reason for abandonment of well or producing formation Commercial quantity of oil not found



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4016 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole with 75 sacks pozmix @ 225' through Halliburton sledge.

6-15-54

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1954
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E Drilling, Inc.
Address 1006 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Clinton Engstrand (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clinton Engstrand
1006 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of June, 1954

My commission expires 10-29-55

Notary Public.

PLUGGING
PT 7 SEC 30 T 21 R 17W
PAGE 39 LINE 4

K & E DRILLING, INC. and
CHEROKEE OIL COMPANY

NO. 1 GORE ESTATE
NW NW NE Sec. 30-21S-17W
Pawnee County, Kansas

Casing
8 5/8" Set @ 230'

Cement
140 Sacks

Comm: 5-17-54
Comp: 6-1-54
Total Depth: 4016'

<u>FORMATION</u>	<u>DEPTH</u>
Shale and shells	0 - 175
Sand	175 - 190
Shale and shells	190 - 230
Shale	230 - 280
Shale and sand streaks	280 - 490
Sand	490 - 620
Sand streaks and shale	620 - 650
Red bed	650 - 860
Red bed - cherty	860 - 1072
Anhydrite	1072 - 1100
Shale and shells	1100 - 1270
Shale and shells	1270 - 1855
Shale and salt	1855 - 1985
Shale and shells	1985 - 2080
Lime and shale	2080 - 2580
Shale and lime	2580 - 2695
Shale, lime and shells	2695 - 2785
Lime and shale	2785 - 3117
Broken lime and shale	3117 - 3172
Lime	3172 - 3227
Lime and shale	3227 - 3285
Lime w/some cherty streaks	3285 - 3345
Lime	3345 - 3410
Lime	3410 - 3442
Heebner	3442 - 3446
Lime	3446 - 3448
Broken lime and shale	3448 - 3501
Shale and br. lime	3501 - 3538
Lime	3538 - 3588
Lime	3588 - 3678
Lime	3678 - 3816
Lime and shale	3816 - 3862
Broken lime and shale	3862 - 3915
Shale and broken lime	3915 - 3918
Conglomerate	3918 - 3926
Arbuckle	3926 - 3950
Lime	3950 - 3974
Lime	3974 - 4016

RECEIVED
STATE CORPORATION COMMISSION
JUN 15 1954

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above information is true and correct,
to the best of my knowledge.

[Handwritten Signature]

Subscribed and sworn to before me this 14 day of June, 1954.

PLUGGING
FILE NO. 307-21-120
BOOK PAGE 39 LINE 4

[Handwritten Signature]
Notary Public

My Commission Expires: 10-29-55