

15-009-2113-00006060075

~~15-009-21113~~ *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15
NE, Sec. 7, T 16 S, R 12 W 18

2310 feet from N/E section line
1650 feet from ~~N/E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Derral Well # 1

Operator: Chief Drilling Co Inc
Name &
Address Suite 905, Century Plaza
Wichita, Ks. 67202

County Barton

Well Total Depth 3746 feet 108.75

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 401'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Ks. 67524

Company to plug at: Hour: 9:30 AM Day: 18 Month: Nov Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order 165 sh 5/8 pos mix - 4% Sol. - 3% lat. Cl., 15 sh Sol,
5 sh. hulla & 8 5/8" plug.

Signed Arthur E. Kelly
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 PM Day: 19 Month: Nov Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 401' w/ 125 sh. 4 1/2" - 3340' w/ 125 sh.

6' open hole. Plugged bottom w/ 5 sh cement, sand 45 sh cement
to 3300'. Shot pipe 1 turn & recovered 2500'.
Pumped in 8 5/8" - 4 sh. hulla, 25 sh cement, 12 sh Sol, 40 sh cement,
3 sh. Sol, 1 sh. hulla, released plug & followed w/ 100 sh cement.
w/ 700 pounds pressure.

Remarks: By Allied Cementing

I hereby certify that the above plugging instructions were given as herein stated
and that I (did ~~not~~) observe this plugging.

RECORDED
STATE CORPORATION COMMISSION

INVOICED

NOV 28 1983 *RWD*
11-28-83

Signed Arthur E. Kelly
(TECHNICIAN) ✓

DATE 12-9-83

INV. NO: 7095-W

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
(Rev. 9-82)