

11-29

To: 1 070763
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,690-0000
C NE NW, SEC. 25, T 21 S, R 20 W EX
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817
Operator: Benson Mineral Group, Inc.
Name & Address 1536 Cole Blvd., Suite 220
Golden, CO 80401

Lease Name Wenzel Well # 2-25
County Pawnee 77.16
Well Total Depth 2374 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7" feet 950

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 29 Month: 11 Year: 19 89

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 2372' Perfs at 2170-2310' (3 sets)

- 1st plug sand back to 2120' and dump 4 sx cement on top of sand through bailer,
- 2nd plug pump 50 sx cement at 980',
- 3rd plug pump 40 sx cement at 400',
- 4th plug pump 10 sx cement at 40',


Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 29 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 2120' and dumped 4 sx cement on top of sand through bailer,

- 2nd plug pumped through casing 15 sx gel, 50 sx cement at 1010',
- 3rd plug pumped 40 sx cement at 440',
- 4th plug pumped 10 sx cement at 40'.



12-5-89

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1230' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-7-89

INV. NO. 26702

Signed Dan Goodwin
(TECHNICIAN)