

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- -145-20,740-0000 ✓

C NW, SEC. 24, T 21 S, R 20 W 1/2

FEET FROM N/S SECTION LINE

FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5817

LEASE NAME Lewis A Well # 1-24

OPERATOR: Benson Mineral Group Inc
NAME & ADDRESS 1536 Cole Blvd.
Suite 220
Golden Colorado 80401

COUNTY Pawnee

WELL TOTAL DEPTH 2330' 75.73 FEET

CONDUCTOR PIPE: SIZE FEET

SURFACE CASING: SIZE 7" FEET 950

ABANDONED OIL WELL _____ GAS WELL INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Hembree Well Service Inc LICENSE NUMBER 6907

ADDRESS 302 E. Sycamore Box 458 Ness City Kansas 67570

COMPANY TO PLUG AT: HOUR: 11:30 DAY: 19 MONTH: August YEAR: 1983

PLUGGING PROPOSAL RECIEVED FROM George Harrison

(COMPANY NAME) Hembree Well Service (PHONE) _____

WERE: To use 60/40 pozmix 2% gel 3% cc
Squeeze Bottom with 35sx cement
Squeeze down 7" with 2sx hulls - 5sx gel
25sx cement - 5sx gel - 1sx hulls - wiper plug -
100 sx cement

PLUGGING PROPOSAL RECEIVED BY Richard W. Lacey
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 12:15pm DAY: 19 MONTH: August YEAR: 1983

ACTUAL PLUGGING REPORT Plugged as proposed in above paragraph

Maximum pump pressure 800 psi

Shut in pressure 500 psi

Recovered 1460' of 4 1/2" production casing

Sunail well cementing pumped the cement

REMARKS: _____

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 8-24-83
INV. NO. 5299-W

STATE CORPORATION COMMISSION FORM CP-2/3
REV. 6-83

AUG 23 1983
CONSERVATION DIVISION
Wichita, Kansas 8-23-83