

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,741-0000

C SW, SEC. 24, T 2/S, R 20 W/E

_____ FEET FROM N/S SECTION LINE

_____ FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5817

LEASE NAME Lewis A Well # 2-24

OPERATOR: Benson Mineral Group Inc
NAME & ADDRESS: 1536 Cole Blvd.
Suite 220
Golden Colorado 80401

COUNTY Pawnee

WELL TOTAL DEPTH 2370 ^{\$77.03} FEET

CONDUCTOR PIPE: SIZE _____ FEET

SURFACE CASING: SIZE 7" FEET 955

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Hembree Well Service Inc LICENSE NUMBER 6907

ADDRESS 302 E. Sycamore Box 458 Ness City Kansas 67530

COMPANY TO PLUG AT: HOUR: 10:30 am DAY: 19 MONTH: August YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM George Harrison

(COMPANY NAME) Hembree Well Service (PHONE) _____

WERE: To use 60/40 pozmix 2% gel 3% acc

Squeeze bottom with 35 sx cement

Squeeze down 7" with 2sx hulls - 5sx gel

25sx cement - 5sx gel - 1sx hulls - wiper plug

100 sx cement

PLUGGING PROPOSAL RECEIVED BY Richard W. Lacey
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 11:10 am DAY: 19 MONTH: August YEAR: 19 83

ACTUAL PLUGGING REPORT Plugged as proposed in above paragraph

Maximum pump pressure 1000 psi

Shut in pressure 600 psi

Recovered 1238' of 4 1/2" production casing

Sun Oil Well Cementing pumped the cement

REMARKS: _____

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1983

CONSERVATION DIVISION
Wichita, Kansas

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

8-23-83

SIGNED Richard W. Lacey
(TECHNICIAN)

INVOICED

DATE 8-24-83

INV. NO. 5298-W

FORM CP-213
REV. 6-83