

1 070106

API NUMBER 15- 145-20,811-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 5, T 21 S, R 20 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Steffen Well # 2 SWD

Operator: Hummon Corporation

County Pawnee 143.00

Name & Address 400 One Main Place
Wichita, KS 67202

Well Total Depth 4400 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4:20 pm Day: 23 Month: December Year: 19 85

Plugging proposal received from Albert Unruh

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3797' PBD 3758' Perfs at 3654-3662'; 3642-3648'; 3606-3616'; 3580-3590'
3560-3570'

1st plug DV tool at 1309' with 350 sx cement

2nd plug squeeze well with 1 sack hulls, 50 sx cement, 15 sx gel, release 8 5/8" rubber
plug and pump 225 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:00 pm Day: 23 Month: December Year: 19 85

ACTUAL PLUGGING REPORT DV Tool at 1309' with 350 sx cement, squeezed well with 1 sack
hulls, 50 sx cement, 10 sx gel, released 8 5/8" rubber plug and pumped 225 sx cement.

12-26-85 - tagged cement at 230' - will fill with ready mix 12-31-85.

Fluid approx. 550'

Maximum pressure 300 psi and shut in - vacuum

Remarks: Used 60/40 Pozmix 2% gel 3% cc.
(If additional description is necessary, use BACK of this form.)

INVOICED

(did not observe this plugging.)

DATE JAN 06 1986

STATE

Signed Dan Gooden
(TECHNICIAN)

INV. NO. 11842

JAN 2 1986

1-2-86