

1070109

copy

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,812-0000
150' S of
C NW NW, SEC. 5, T 21 S, R 20 W/8
150' S of
4620 feet from S section line
4620 feet from E section line

Rec'd
1-1-96

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Steffen Well # 3

Operator: Hummon Corporation

County Pawnee

Name & Address 400 One Main Place

Well Total Depth 4387 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:00 pm Day: 23 Month: December Year: 19 85

Plugging proposal received from Albert Unruh

(company name) Kelso (phone) 316-938-2457

logs: 4 1/2" at 4384' Perfs at 4313-4315'; 4300-4303'; 4311-4312'

DV Tool at 1327' with 400 sx cement

Squeeze well with 1 sack hulls, 50 sx cement, 20 sx gel and 125 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00 pm Day: 23 Month: December Year: 19 85

ACTUAL PLUGGING REPORT DV Tool at 1327' with 400 sx cement. Squeezed well with 1 sack
hulls, 50 sx cement, 14 sx gel, released 8 5/8" rubber plug and pumped 110 sx cement.

Fluid level approximately 4000'

Maximum pressure 2700 psi and shut in 2100 psi

Remarks: No Recovery. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Dan Groder
(TECHNICIAN)

KCC/KDHE JOINT OIL/GAS REGULATORY OFFICE

copy

DATE 1-9-86

- New Situation
- Response to Request
- Follow-up

OPERATOR Hummon Corp. # 5050

NAME One Main Place, Str. 400

LOCATION 150's, NW 1/4, SEC 5, T 21 S, R 20 E F

ADDRESS Wichita, Ks. 67202

LEASE Steffen Well # 3

PHONE NO. OPER. 316-263-8521 OTHER

COUNTY Pawnee

REASON FOR INVESTIGATION: Check back on plugged well.

PROBLEM: Salt water at surface. Ineffective plugging.

LEASE INSPECTION

PERSON(S) CONTACTED:

FINDINGS: This well was plugged on 12-23-85. DV @ 1327' @ 400 sx. cem. TD @ 4387'. The well was plugged through 4 1/2" casing @ 1 hull, 50 sx. cem., 14 gel, plug, 110 sx. cem., 60/40 poz. 2% gel and 3% CC. Fluid level was approx. 4000'. Max. pressure during plugging was 2700 lbs. @ 2100 lbs. shut in. Kelso Casing was the plugging contractor and Allied was the Cementer.

COMPLAINT

I checked the lease on 1-9-86. The cellar had been filled in @ dirt. Where the cellar had been, there was a sunken place with approx. 1/4 bbl. salt water in it. I bailed out the water @ a bucket. The hole re-filled from the bottom shortly.

photos taken:

ACTION/RECOMMENDATIONS: recommmend re-plugging a.s.a.p.

FIELD REPORT

Retain 1 copy Joint District Office
 Send 1 copy Conservation Division
 Send 1 copy KDHE/Topeka if appropriate

By Dan Goodrow

Talked to Mike Kelso by phone, 10:00 AM - 1-10-86.
Mr. Kelso stated that he would go out to the location
and have a look at it that same day. He would call
me back with his findings.

Kelso dug out the cellar and welded a cap onto the 8 5/8" surface pipe.
The cap has a 3" valve.

Kelso contracted Allied Cem. to pump 125 sx. cem. (60/40 pot. 67% gel) down
the 8 5/8". 1-16-86. End cemented 1-16-86

copy

15-145.20812-0000