

See attached field report dated 1-9-86

1 070107

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,730-0000  
75' W of  
C SW NW, SEC. 5, T 21 S, R 20 W  
75' W of  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050  
Operator: Hummon Corporation  
Name: Hummon Corporation  
Address: 400 One Main Place  
Wichita, KS 67202

Lease Name Steffen Well # 1  
County Pawnee 143.16  
Well Total Depth 4405 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 23 Month: December Year: 19 85

Plugging proposal received from Albert Unruh

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4404' PBTD 4370' Perfs at 4316-18'; 4336-4338'; 4330-4332'; 4603-4609'

2-Stage - 900' of cement pumped down through annulus

Squeeze well with 1 sack hulls, 50 sx cement 20 sx gel and 125 sx cement.

Plugging Proposal Received by J. H. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 am Day: 23 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 2-staged. 900' of cement pumped down through annulus.

Squeezed well with 1 sack hulls, 50 sx cement, 10 sx gel, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 1700 psi and shut in 1300 psi

Remarks: No recovery. Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 06 1986

INV. NO. 11845

JAN 2 1986 signed Dan Gordon (TECHNICIAN)

Wichita, Kansas 1-2-86