

To: 1070109
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,812-0005
150' S of _____
C NW NW, SEC. 5, T 21 S, R 20 W/E
150' S of _____
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050
Operator: Hummon Corporation
Name & Address 400 One Main Place
Wichita, KS 67202

Lease Name Steffen Well # 3
County Pawnee 142.58
Well Total Depth 4387 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:00 pm Day: 23 Month: December Year: 19 85

Plugging proposal received from Albert Unruh

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4384' Perfs at 4313-4315'; 4300-4303'; 4311-4312'
DV Tool at 1327' with 400 sx cement

Squeeze well with 1 sack hulls, 50 sx cement, 20 sx gel, and 125 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 23 Month: December Year: 19 85

ACTUAL PLUGGING REPORT DV Tool at 1327' with 400 sx cement. Squeezed well with 1 sack hulls, 50 sx cement, 14 sx gel, released ¹⁴ 8 5/8" rubber plug and pumped 110 sx cement. Fluid level approximately 4000'

Maximum pressure 2700 psi and shut in 2100 psi

Remarks: No Recovery. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 06 1986
INV. NO. 11844

JAN 2 1986

Signed Don Grodin
(TECHNICIAN)