

235 R

12-13

1 120365

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,427-0000

C SE, SEC. 13, T 21 S, R 20 W/EX

1320 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Bauer Well # 1-13

Operator: Benson Mineral Group, Inc.

County Pawnee 71.89

Name & Address 1536 Cole Blvd., Suite 220

Well Total Depth 2212 feet

Golden, CO 80401

Conductor Pipe: Size feet

Surface Casing: Size 7" feet 317

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 4 Month: 12 Year: 19 89

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 2210' Perfs 2173-83'

1st plug sand back to 2120' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 15 sx gel and 50 sx cement at 1300',

3rd plug pump 50 sx cement at 650', 4th plug at 330' with 40 sx cement,

5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:30 p.m. Day: 13 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 2120' with 4 sx cement on top

of sand through dump bailer. Shot 4 1/2" casing at 1350' and 1230', layed down 7 joints, well

flowing 3 BPM. 2nd plug pumped in 5 sx gel and 50 sx cement at 950', shut in at 175#. Set

24 hours, well was dead. Shot 4 1/2" at 625' and the well flowed 3 BPM, TOC @ 850', 3rd plug

pumped in 3 sx gel and 50 sx cement, shut in @ 250#, let set 8 days, ran line-TOC @ 500'.

Shot 4 1/2" at 350'. 4th plug pumped in 108 sx cement, did not circulate. Pumping pressure 0-600 psi and shut in 200 psi. Ran line on 1/9/90. Cement at top of 4 1/2" casing.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 210' of 4 1/2" casing

(if additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE JAN 26 1990

INV. NO. 27178

Signed [Signature] CONSERVATION DIVISION (TECHNICIAN) Wichita, Kansas

RECEIVED STATE CORPORATION COMMISSION

JAN 23 1990

1-23-90