

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- -145-20796-0000

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5817

OPERATOR: Benson Mineral Group Inc
NAME & ADDRESS 1536 Cole Blvd.
Suite 220
Golden Colorado
80401

100' N C-SE SEC. 11, T21 S, R20 W/E

_____ FEET FROM N/S SECTION LINE

_____ FEET FROM W/E SECTION LINE

LEASE NAME Lipp WELL # 1-11 Twin

COUNTY Pawnee

WELL TOTAL DEPTH 2409 FEET ^{878.29}

CONDUCTOR PIPE: SIZE _____ FEET

SURFACE CASING: SIZE 7" FEET 959

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Hembree Well Service Inc LICENSE NUMBER 6907

ADDRESS 302 E Sycamore Box 458 Ness City Kansas 67530

COMPANY TO PLUG AT: HOUR: 2:00 DAY: 19 MONTH: August YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM George Harrison

(COMPANY NAME) Hembree Well Service Inc (PHONE) _____

WERE: To use 60/40 pozmix 2% gel 3% cc
Squeeze bottom with 35 sx cement
Pump down 7" with 2 sx hulls - 5 sx gel - 25 sx
cement - 5 sx gel - 1 sx hulls - wiper plug -
100 sx cement

PLUGGING PROPOSAL RECEIVED BY Richard W. Lacey
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 3:15 pm DAY: 19 MONTH: August YEAR: 1983

ACTUAL PLUGGING REPORT Plugged as proposed in above paragraph

Maximum pump pressure 600 psi

Shut in pressure 300 psi

Recovered 1194' of 4 1/2" production casing

Sun oil well cementing pumped the cement

REMARKS: _____

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1983

8-23-83

CONSERVATION DIVISION
Wichita, Kansas

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey
(TECHNICIAN)

INVOICED

DATE 8-24-83

INV. NO. 5296-W

FORM CP-2/3
REV. 6-83