

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-20,767-0000  
C. NE 1/4 SEC. 11, T21S, R20W

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ FEET FROM N/S SECTION LINE

\_\_\_\_\_ FEET FROM W/E SECTION LINE

OPERATOR LICENSE # 5817

LEASE NAME BRYANT A WELL # 1-11

OPERATOR: BENSON MINERAL GROUP, INC  
NAME & ADDRESS 1536 Cole Blvd.  
Suite 220, Golden, CO 80401

COUNTY PAWNEE

WELL TOTAL DEPTH 2369 \$ 76.99 FEET

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET

SURFACE CASING: SIZE 7" FEET 967

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Hemtree Well Service LICENSE NUMBER 6907

ADDRESS 302 E. Sycamore, Box 458, Ness City, KS 67560

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 22 MONTH: Aug YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM William T. Philo

(COMPANY NAME) BENSON (PHONE) \_\_\_\_\_

WERE: 4 1/2" set @ 2769 w/ 1034' recovered - Perfo @ 2215' -

Bottom plugged w/ 35 sq cmt - top plug pump w/  
20 sq hells, 5 sq gel, 25 sq cmt, 5 sq gel, 1 sq hells, Plug,  
100 sq cmt, using 60/40 Poz mix w/ 2% gel - 3% ace

PLUGGING PROPOSAL RECEIVED BY R Barlittan  
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 10:15 AM DAY: 22 MONTH: Aug YEAR: 1983

ACTUAL PLUGGING REPORT plugged as proposed,

max. pump pressure @ 1000#  
Shut in @ 750#

Cementing by Sun Cementing

8-26-83

REMARKS: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

AUG 26 1983

CONSERVATION DIVISION  
Wichita, Kansas

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

SIGNED R Barlittan  
(TECHNICIAN)

INVOICED

DATE 8-26-83

INV. NO. 5342-U

FORM CP-2/3  
REV. 6-83