

1050420

API NUMBER 15- 083-20,844-0000 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SW, SEC. 8; T 21 S, R 21 W/EX
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5753

Lease Name Lewis Well # 1

Operator: W. E. Carl
Name & Address: 500 North Water, # 800
CCNB Center North
Corpus Christi, TX 78471

County Hodgeman 142.25
Well Total Depth 4377 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 465 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Ness County Well Service License Number 7527

Address P. O. Box J, Ness City, KS 67560

Company to plug at: Hour: 9:30am Day: 31 Month: December Year: 19 84

Plugging proposal received from Dennis Barry

(company name) W. E. Carl (phone) 913-628-3651

were: 5 1/2" set at 4387' Perfs at 4298-4300'

1st plug sand back to 4248' and dump 5 sx cement on top of sand through bailer

2nd plug pump 2 sx hulls, 10 sx gel, 60 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 31 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4387' Perfs at 4298-4300'

1st plug sanded back to 4248' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 2 sx hulls, 10 sx gel, 60 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 1000 psi and shut in 400 psi

JAN 07 1985 1-7-85

Remarks: Used 60/40 Pozmix 2% gel 3% cc

(If additional description is necessary, use BACKR/CONDIVISION Form.) Wichita, Kansas

INVOICED (check name) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 1-16-85

INV. NO. 6501 12-31