

To: 1 052107 2-7 -API NUMBER 15-145-21,440-0000
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION App. E/2 NE NE, SEC. 21, T 21 S, R 17 W/X
130 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License / 31777

Operator: Horizon Geophysical Corporation
Name: 3608 Clancy Lane
Address: El Paso, TX 79927

4637 feet from S section line
355 feet from E section line
Lease Name Unruh Well # 1
County Pawnee 80.24
Well Total Depth 2469 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1117

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ O&A ☐

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 7 Month: 2 Year: 1997

Plugging proposal received from Mike Kelso
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 2468' w/100 sx cement, Open hole 2468-69'

1st plug sand back to 2400' and dump 5 sx cement on top of sand through bailer,

2nd plug at 1117' with 50 sx cement,

3rd plug at 600' with 25 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 1:30 p.m. Day: 7 Month: 2 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 2400' and dumped 5 sx cement on top of sand through bailer,

Spotted plugs through casing:

2nd plug at 1117' with 50 sx cement,

3rd plug at 600' with 25 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 2-19-97
INV. NO. 47593

Signed Richard M. Lacy
(TECHNICIAN)