

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21043-0000

SW SE NE, Sec. 10, T 21 S, R 18 W/X

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7930

Lease Name Fleske Well # 1-10

Operator: Merit Energy Corp.
Name & 1750 Energy Center
Address 717 17th Street
Denver, CO 80202

County Pawnee

Well Total Depth 4056' feet \$1,31.82

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1,004

Abandoned Oil Well x Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 25 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mike Gomez

(company name) Kelso Casing Pulling (phone) 316-938-2416

were: 1st plug sand bottom back to 3720' and dump 4 sx cement on sand through
bailer. 2nd plug pump through head in sequence 3 sx hulls, 10 sx gel, 75 sx cement,
15 sx gel, 1 sack hulls and release 8 5/8" plug and pump another 125 sx cement.

Signed Richard M. Lucey
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 25 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug sand bottom back to 3720' and dump 4 sx cement on
sand through bailer. 2nd plug pump through head in sequence 3 sx hulls, 10 sx gel,
75 sx cement, 15 sx gel, 1 sack hulls and release 8 5/8" plug and pump another
125 sx cement.

Remarks: They recovered 2810' of 4 1/2" production casing. Sun cementing
accomplished the job with 60/40 Pozmix, 2% gel, 3% cc. Maximum pressure 900# and
shut in pressure at 500#.

2-2-84

RECEIVED
STATE CORPORATION COMMISSION
FEB 02 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as here stated
and that I (did / ~~XXXXXX~~) observe this plugging.

Signed Richard M. Lucey
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 2-6-84

INV. NO. 0084