

KANSAS

15-009-20218-0000

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 9 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name Weber "N" Well No. # 1

Location NW NW NE Sec. 7 Twp. 16 Rge. 12 (E)    (W) W

County Barton Total Depth 3349

Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X

Other well as hereafter indicated:   

Plugging Contractor: Garvey Drilling Company

Address: Route # 2, Great Bend, Kansas 67530 License No.   

Operation Completed: Hour 10:15PM Day 5 Month 5 Year 1968

The Above well was plugged as follows:

8 5/8" 369' Cwc.  
Circulated hole with heavy mud to 500', set plug, & displaced 70 sax cement thru  
drill pipe. Mud to 350', set plug, & displaced 25 sax cement thru drill pipe.  
Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with Globe Cementing  
Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Lewis  
Well Plugging Supervisor

INVOICED

DATE 5/9/68  
INV. NO. 7720-w