

40
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-009-00261-0000

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1964
02-17-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Thomas H. Allan

Complete Address: R. R. # 1, Great Bend, Kansas

Lease Name Stiles Well No. # 1

Location NW NE SW Sec. 7 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3357

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Gasing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 4 PM Day 14 Month 2 Year 1964

The Above well was plugged as follows:

8 5/8" 425' Gwc.

Sanded hole back to 3340' & dumped 5 sax cement with dump bailer.

Pulled pipe. Bailed hole down to 350'; set rock bridge; displaced 25

sax cement. Mud to 40'; set rock bridge & displaced 10 sax cement,

cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2/18/64

INV. NO. 8662-u