

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 10-24-68

RECEIVED
STATE CORPORATION COMMISSION

JUL 03 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -145 -20,519-0000 (of this well)

Operator's Full Name Sterling Drlg. Co.

Complete Address Box 129, Sterling, Kansas

Lease Name Woods Well No. ~~4325~~ 1

Location C SW Sec. 1 Twp. 21 Rge. (E) (W) 20

County Pawnee Total Depth 4325'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Husky Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 12:45 A Day 1 Month 7 Year 1978

The above well was plugged as follows:

RTD 4325' 8 5/8 csg set 294' cwc Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 420' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7-5-78
INV. NO. 7605-W

Signed: Leo Massey
Well Plugging Supervisor