

15.145.19036-0000

Form CP-3
Rev. 6-26-62

R
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jones-Gebert Oil Co
Complete Address: 205 Central Bldg Wichita, Kans
Lease Name Steffen Well No. 1
Location CSE SW Sec. 8 Twp. 21 Rge. (E) (W) 20
County Pawnee Total Depth 4290
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Apex Casing Pulling & Halliburton Cementing
Address: Holsington, Kans License No. 544
Operation Completed: Hour 12:30PM Day 18 Month 5 Year 64

The Above well was plugged as follows:

8 5/8" 290' circulated with cement - 4 1/2" 4289' with 150 sax cement - Perforated 4250'

Sand back to 4230', set 3 sax cement with dump bailer - pulled 2373' 4 1/2" - pumped hole full heavy gel mud (40 sax Gel), pumped wiper plug followed by 100 sax cement - cement to 0'

~~Mudding and cementing by Halliburton Co - 300# pump pressure.~~

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. P. Roberts
Well-Plugging Supervisor

DATE 5/21/64

INV. NO. 9185-W