

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1975

CONSERVATION DIVISION
Wichita, Kansas

5-27-75

Operator's Full Name Palomino Petroleum
Complete Address 304 Insurance Bldg., Wichita, Kansas 67202
Lease Name Steffem Well No. 11
Location E/2 E/2 SW Sec. 8 Twp. 21 Rge. (E) (W) 20
County Pawnee Total Depth 4258'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Dunbar Pipe Pulling
Address Wichita, Kansas License No. 709
Operation Completed: Hour 11:45 P. Day 22 Month 5 Year 1975

The above well was plugged as follows:

Total Depth 4258' 8 5/8 csg set 320' cwc 250 sk.
4 1/2 csg set 4256' cw 250 sk cem.
4 1/2 csg FBTD 4244' & perf. (4232-4242)
Filled 4 1/2 csg With snd (4258'-4200') dumped 4 sk cem W/dump bailer. (4200-4165)
Cutoff & recovered 2350' of 4 1/2 csg.
Mixed & pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls -released plug &
& 125 sk comm cem. by HOWCO. PP 400 lbs. SIP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Murray
Well Plugging Supervisor

INVOICED

DATE 5/29/75

INV. NO. 1377-W