

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 28 Twp. 21 Rge. 17 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SW NE
Lease Owner Dreiling & Hiko Bell Mining & Oil Company
Lease Name Kirby Well No. 1
Office Address Route 2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-18 1969
Application for plugging filed 3-18 1969
Application for plugging approved 3-18 1969
Plugging commenced 3-18 1969
Plugging completed 3-18 1969
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	1053'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st. plug was set @ 360' with 25 sacks cement
2nd. plug was set @ 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

SUBSCRIBED AND SWORN TO before me this 21st. day of March, 1969

My commission expires September 19, 1970
Joseph A. Hess Notary Public.
JOSEPH A. HESS



L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

15.145-20107-0000

WELL LOG

Company	Dreiling & Hiko Bell Mining & Oil Company Route 2 Victoria, Kansas 67671	Sec. 28	Twp. 21	Rng. 17
Farm	Kirby No. 1	Location	SW NE	
Total Depth	3950'	County	Pawnee	
Comm.	3-10-69	Comp.	3-18-69	Elevation: 2053' K. B.
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas 67671			2050' D. F.
		Casing Record	Cement Record	2048' G. R.
		1053' - 8 5/8'	400 sacks cement	Production: D & A

Figures Indicate Bottom of Formations

0'	435'	Surface Clay & Shale
435'	605'	Sand
605'	1049'	Redbed
1049'	1066'	Anhy. Shale
1066'	1655'	Shale & Lime
1655'	2640'	Lime
2640'	2880'	Shale & Lime
2880'	3350'	Lime
3350'	3470'	Shale & Lime
3470'	3530'	Lime
3530'	3909'	Shale & Lime
3909'	3950'	Lime
3950'	T.D.	Lime & Chert

RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1969
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Kirby #1.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 21st. day of March 1969.

Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC



My commission expires: September 19, 1970