

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 27 TWP. 21s RGE. 17w E/W
Location as in quarters or footage from lines:
C NW SE

Locate Well
correctly on above
Section Platt.

Lease Owner Beren Corporation
Lease Name Andree #1 Well No. _____
Office Address 970 Fourth Financial Center, Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 3/19/83
Plugging completed 4/19/83
Reason for abandonment of well or producing formation _____

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 2045'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				7"	764'	none
				4 1/2"	2044'	1504'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pumped bottom with 25 sacks 50/50 poz. 2% gel 3% c.c. to 1900'. Well on
slight vacuum. Shot casing at 1741' & 1623', & 1515'. Pulled total of 46
joints. Plugged well with 1 hull, 50 cement, 5 gel, 100 sacks cement, 50/50
poz. 4% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 83



Irene Hoover
Notary Public.

My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1983

CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- ANDREE #1
Located: C NW SE, Section 27-21S-17W, Pawnee County,
Kansas

OWNER: Eeren Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 16, 1977
COMPLETED: December 29, 1977

TOTAL DEPTH: 2045'

LOG	CASING RECORD
0 - 210 Clay and Shale	Ran 25 joints 7", 20# new casing, 762.25' pipe set at 763.75' C.L. Cemented with
210 - 720 Shale and Red Bed	325 sacks 60/40 Pozmix with 3% ca. Plug down at 8:00 PM, 12-18-77.
720 - 1040 Shale	
1040 - 1066 Anhydrite	
1066 - 1962 Shale	
1962 - 2020 Shale and Lime	
2020 - 2045 Shale	Ran 64 joints 4 1/2" OD Casing, 2053' cemented at 2044' C.L. with 25 sacks 50/50 Pozmix, 10# gilsonite per sack, followed with 50 sacks 60/40 Pozmix with 18% salt. Plug down at 3:15 AM, 12-29-77, by Sun Cementing Co.

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1983

CONSERVATION DIVISION
Wichita, Kansas