

15-145-20683-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Pawnee SEC. 26 TWP. 21s RGE. 17w E/W  
 Location as in quarters or footage from lines:  
NW SW NW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Beren Corporation  
 Lease Name Josefiak #1 Well No. \_\_\_\_\_  
 Office Address 970 Fourth Financial Center, Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 3/16/83  
 Plugging completed 4/19/83  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 2082'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				7"	827'	none
				4 1/2"	2081'	1119'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Pumped bottom with 25 sacks common to 1900', well on vacum. Shot casing  
at 1243', & 1127'. Pulled 26 joints. Plugged well with 1 hull, 50 cement,  
5 gel, 100 cement, 50/50 poz. 4% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 347, Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 83

My Commission expires: \_\_\_\_\_



[Signature]  
 Notary Public.  
 STATE CORPORATION COMMISSION

APR 21 1983

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- JOSEFIAK #1  
Located: NW SW NW, Section 26-21S-17W, Pawnee County,  
Kansas

OWNER: Beren Corporation  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 28, 1980  
COMPLETED: June 1, 1980

TOTAL DEPTH: 2082'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 492 Sand and Gravel	Ran 20 joints new 7" OD casing. 826.19' pipe set at 827' G.L. Cemented with 250 sacks Howco Lite, 100 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 10:45 AM, 5-29-80, by Howco.
492 - 830 Lime and Shale	
830 - 1022 Shale	
1022 - 2082 Lime and Shale	Ran 54 joints new 4 1/2" casing. 2091' set at 2081' G.L. Cemented with 200 sacks 60/40 Pozmix with 10# salt, 10# gilsonite, 2% gel and 3/4 of 1% CFR-2. Plug down at 6:00 AM, 6-1-80.

Deviation Surveys: 3/4° at 831'  
1 1/2° at 2082'

RECEIVED  
STATE CORPORATION COMMISSION

FEB 28 1983

CONSERVATION DIVISION  
Wichita, Kansas