


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pawnee County, Sec. 10 Twp. 21 Rge. 18 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Don Burnett
Lease Name Browne Well No. 1
Office Address Larned, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 11-27-65 19
Plugging completed 12-2-65 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation Depth to top Bottom Total Depth of Well 4026 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	227'	None
				4-1/2"	4014'	3279'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4026', pushed plug to 3480', ran 30 gallon of sand and dumped 3 sacks of cement with dump bailer. Pulled 85 jts. of 4 1/2" casing and pumped in 5 sacks of weight mud and 10 sacks of gel mud. Pulled balance of 4 1/2" casing and pumped 100 sacks of cement to cap well.

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1965

PLUGGING COMPLETE.

CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of December, 1965

My commission expires May 20, 1968
Milton J. Volin Notary Public.