

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

APR 16 1982

15-185-21296-0000

CONSERVATION DIVISION
Give All Information Completely
Make Required Affidavit

WELL PLUGGING RECORD

4-16-82

COUNTY Stafford SEC. 16 TWP. 23S RGE. 14W E/W
Location as in quarters or footage from lines:
NE SW SW

Lease Owner L.D. Drilling, Inc.
Lease Name Watson #1 Well No. _____
Office Address Route 1 Box 183-B Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 4-5-82
Plugging completed 4-8-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz
Producing formation _____ Depth to top _____ bottom T.D. 4100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	424'	none
				4-1/2"	4099'	3037'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 3600' and ran 4 sacks cement. Shot casing @3218',
3109' and 3024'. Pulled a total of 76 joints of 4-1/2" casing. Plugged well with
5 sacks hulls, 25 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% cc.
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 19 82



Irene Hoover
Notary Public.

My Commission expires: _____

DRILLERS' WELL LOG

15-195-21296-000

DATE COMMENCED: May 29, 1981
DATE COMPLETED: June 4, 1981

PRODUCTION, INC.
"WATSON # 1"
NE¹SW SW
Sec 16-T23S-R14W
Stafford County, Kansas

API # 15-185-21,296

ELEVATION: 1977 K.B.

0 - 424'	Sand, Shale
424 - 1224'	Shale
1224 - 2595'	Shale, Lime
2595 - 3230'	Lime, Shale
3230 - 3418'	Shale, Lime
3418 - 3422'	Shale
3422 - 3438'	Lime, Shale
3438 - 3456'	Lime
3456 - 3551'	Shale
3551 - 3563'	Lime, Shale
3563 - 3800'	Lime
3800 - 3876'	Lime, Shale
3876 - 3944'	Lime, Shale, Chert
3944 - 4004'	Lime
4004 - 4049'	Sand
4049 - 4100'	Dolomite
4100'	RTD

FORMATION TOPS:

Heebner	3418
Toronto	3438
Douglas	3456
Brown Lime	3551
Lansing	3563
Base K.C.	3800
Mississippian	3876
Viola	3944
Simpson Sand	4004
Arbuckle	4049
RTD	4100

SURFACE PIPE:
Set new 8 5/8", 24#
at 424' w/325 sacks 60/40
Pozmix, 2% Gel, 3% cc.

PRODUCTION PIPE:
Ran 103 jts new 10 1/2#
4 1/2" casing @ 4099'
w/175 sacks 50/50 Poz.
600# salt

RECEIVED
STATE CORPORATION COMMISSION

MAR 10 1982

CONSERVATION DIVISION
Wichita Kansas

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON

I, Kenneth Roach, of Mustang Drilling & Exploration, Inc., do state
that the above is true and correct to the best of my knowledge.

Kenneth Roach
Kenneth Roach

Subscribed and sworn to before me this 19th day of June, 1981.

Beverly Shewbart
Beverly Shewbart, Notary Public

BEVERLY SHEWBART
Barton County, Kansas
My Appt. Exp. _____

My Appointment Expires: April 14, 1982