


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD 15-185-19459-0000

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 17 Twp. 23S Rge. 14 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C NW SE SE

Lease Owner Ralph R. Rhyne

Lease Name Cornwell Well No. 1

Office Address P. O. Box 385 Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 12-27-68 19

Application for plugging approved 12-28-68 19

Plugging commenced 1-19-69 19

Plugging completed 2-1-69 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren

Producing formation Depth to top Bottom Total Depth of Well 1061 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	266	None
				1 1/2	None	3679

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 6 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar.

Killed gas. Sanded to 3850'. Dumped 3 sacks of cement. Shot pipe at 3700'. Working pipe.

Circulating. Spotted 75 bbl. of oil. Working pipe.

Pulling pipe.

Pulled casing head. Shut in water. Squeezed well with 10 sacks of mud and 75 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of February, 1969

My commission expires May 27, 1969

Notary Public.

# DRILLER'S WELL LOG

15-185-1945A-0000

OPERATOR: K & E DRILLING, INC.  
719 Union Center Building  
Wichita 2, Kansas

WELL NAME: #1 CORNWELL

LOCATION: C NW SE SE, Sec.17-23S-14W  
Stafford Co., Kansas

CONTRACTOR:

**K & E DRILLING, INC.**  
719 UNION CENTER BLDG.  
WICHITA, KANSAS

COMMENCED: 11-20-62

CASING RECORD: 8-5/8" @ 266' w/225' SX.  
4-1/2" @ 3968' w/75' SX.

COMPLETED: 11-29-62

ELEVATION: 1962 DF, 1965 KB

ROTARY TOTAL DEPTH: 4061

PRODUCTION: Kinderhook

## FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Soil & Clay	25
Sand	80
Clay	180
Shale	335
Sand	375
Red Bed & Blue Shale	870
Shale & Chalky Lime	875
Anhydrite	934
Sand & Shale	1130
Shale & Shells	1710
Lime & Shale	1975
Lime & Shale	2210
Lime	2340
Lime & Shale	2715
Shale & Lime & Shells	2905
Lime & Shale	3215
Lime	3965
Lime & Shale	4015
Lime & Chert	4061

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1968  
CONSERVATION DIVISION  
Wichita, Kansas

## CERTIFICATION

State of KANSAS }  
County of SEDGWICK } ss:

I, H. L. Wilson, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

H. L. Wilson  
H. L. Wilson

Subscribed and sworn to before me this 7th day of December 19 62.

Julene M. Bannon  
Julene M. Bannon Notary Public.

My Commission expires: August 30, 1965.

