

15-185-20374-0000 9

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 17 Twp. 23S Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines NW NE SE
Lease Owner Rosen Oil Corporation
Lease Name Cornwell "A" Well No. 1
Office Address 200 Sutton Place, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 6, 19 71
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced October 6, 19 71
Plugging completed October 6, 19 71
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (G. Russell Biberstein of Attica)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4077 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	259'	8-5/8"	9/28/71	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 650 Feet,
Plug and 40 sax Cement; Mud to 240 Feet,
Plug and 30 sax Cement; Mud to 40 Feet,
1/2 sax Hulls, Plug bridged and 10 sax
Cement to Base of Cellar; 2 sax Cement
in Rat Hole. Job Completed @ 11:45 P.M.

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing Co.
Address Box 207, Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Clarence Michael of Sage Drilling Co. (employee of owner) or (contractor or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Clarence Michael
500 Bitting Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 7th day of October, 19 71
Louise K. Whitted
Notary Public.
My commission expires November 26, 1974.

QR

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

CORNWELL "A" NO. 1

15-185-20374-0000


CASING RECORD:	OPERATOR: Rosen Oil Corporation	DESCRIPTION:
8-5/8" @ 259' w/200 sax cement	CONTRACTOR: Sage Drilling Co.	NW NE SE Sec. 17-23S-14W Stafford Co., Kansas
TOTAL DEPTH: 4077'	COMMENCED: September 27, 1971	ELEVATION: 1974KB
	COMPLETED: October 6, 1971	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	180	
Red Bed	180	830	
Shale	830	1710	
Lime & Shale	1710	3574	
Lime	3574	3838	
Lime & Shale	3838	3930	
Lime & Sand	3930	4005	
Lime	4005	4050	
Lime & Shale	4050	4077	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By *Clarence Smid*



Subscribed and sworn to before me this 7th day of October, 1971.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.