

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

15-185-26017-00-01

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County, Sec. 17 Twp. 23 S Rge. 14 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
150' S of SE NE SE


Lease Owner TGT Petroleum Corporation  
Lease Name Cornwell Well No. 1  
Office Address 209 E. William St., Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202  
oil

Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced November 17 1977  
Plugging completed November 19 1977  
Reason for abandonment of well or producing formation  
depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Jasper Metz  
Producing formation Depth to top Bottom Total Depth of Well 3929'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			250'	8 5/8"	250'	none
			3910'	4 1/2"	3910'	880.65

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back to 3880' and dumped 4 sacks of cement.

Halliburton Services plugged well pumping in 3 sacks of hulls, 20 sacks of gel and 100 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 23 1977

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor PIPE PULLERS, INC.  
Box 128, Ellinwood, Kansas 67526

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS COUNTY OF BARTON  
Evelyn Roth (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November, 1977

My commission expires

JENNY KASSELMAN  
NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
MY COMM. EXP. JULY 16, 1978

Jenny Kasselmann  
Notary Public.

KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

*Want Copy on Demand*  
**COPY**

COMPANY J. M. STEWART

15-185-20017-000 SEC. 17 T. 23 R. 14W  
 LOC. 150' S of SE NE SE

FARM Cornwell

NO. 1

TOTAL DEPTH 3929

COUNTY Stafford


COMM. 3-8-67

COMP. 3-18-67

SHOT OR TREATED

CONTRACTOR Hellar Drlg.

ISSUED 4-8-67



CASING

20 10  
 15 8 5/8" @ 250' w/200 sx  
 12 6  
 13 5

ELEVATION 1983' KB

PRODUCTION DRY/KIND SAND

FIGURES INDICATE BOTTOM OF FORMATIONS

0-250	Surface Sand & Shale	
250-875	Shale & Red Bed w/sand streaks	
875-892	Shale	
892-910	Anhydrite	
910-1600	Shale, Red Bed & Salt Section	
1600-1845	Shale & Lime	
1845-2000	Salt Section & Cherty Lime	
2000-2205	Cherty Lime	
2205-2345	Cherty Lime & Shale	
2345-3113	Lime & Shale	
3113-3244	Topeka Lime & Shale	TOPS: SCOUT
3244-3489	Lime & Shale	
3489-3552	Shale	Anhydrite 892
3552-3555	Shale & Lime	Heebner 3421
3555-3596	Lime	Toronto 3439
3596-3644	Lime & Shale	Douglas 3456
3644-3720	K. C. Lime	Brown Lime 3552
3720-3780	Lime	Lansing 3565
3780-3827	K. C. Lime	Base Kansas City 3800
3827-3895	Lime	Mississippi 3874
3895-3905	Miss. Chert & Lime	Kinderhook Sand 3908
3905-3929	Sand	
3929	Rotary Total Depth	

D & A

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Cornwell, located 150' S. SE/4 NE/4 SE/4 Sec. 17-23S-14W, Stafford County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

SEP 22 1967

HELLAR DRILLING COMPANY, INC.