



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

*Reed*  
*1-31-68*

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Butts of Mull Drilling Company has this date requested permission to plug the following described well:

Mr. Butts guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.,

Complete Address: 1625 Wichita Plaza Wichita, Ks.

Lease Name: Ideker Well No. 2

Location: SW SE SE Sec. 2 Twp. 21 Rge. 19 (E)(W) X

County: Pawnee Total Depth 4260' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Mull was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 540' and displace  
70 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2  
sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cem.

Very truly yours,

*[Signature]*  
 Conservation Division Agent