



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
CONSERVATION DIVISION  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 4 1965

CONSERVATION DIVISION  
Wichita, Kansas

5-4-65

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling has this date requested permission to plug the following described well:

Mr. Sunray D X Oil Co guarantees payment of the plugging fee.

Operator's full Name: Sunray D X Oil Co

Complete Address: Box 729 Great Bend, Kans  
505 Central Bldg. Wichita, Kans.

Lease Name: Latas Well No. 1

Location: SW NE NE Sec. 5 Twp. 21 Rge. (E) (W) 19

County Pawnee Total Depth 4420 Oil Well

Gas Well  Input Well  SWD Well  D & A x Lost Hole

Mr.  was instructed to plug the well as follows:

8 5/8" 388' 5 1/2" 4418' with 175 sax cement

Sand to 4300', set 5 sax cement with dump bailer.

Pull pipe to 500' circulated with heavy mud, set 20 sax cement at 540'  
heavy mud to 240', set 20 sax cement at 240', heavy mud to 35', cement  
35' to 0'

Very truly yours,

[Signature]  
Conservation Division Agent