



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-185-20374-0002

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Rankin of Sage Drlg. Co. has this date requested permission to plug the following described well:

Mr. Rankin guarantees payment of the plugging fee.

Operator's full Name: Rosen Oil Corporation

Complete Address: 200 Sutton Place Wichita, Ks

Lease Name: Cornwell A Well No. 1

Location: NW/NE/SE Sec. 17 Twp. 23s Rge. 14 (E)(W) W

County: Stafford Total Depth 4077 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rankin was instructed to plug the well as follows:
259ft 8 5/8 surface pipe cemented with 225 sacks. Pump 40
sacks cement to 650 ft. 2nd plug at 240 ft with 30 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement
to surface. 2 sacks cement in rat hole.

Pumped by Allied Cementing Co. Russell, Ks

Very truly yours,

[Signature]
Conservation Division Agent