

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

MAR 20 1967

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-185-20017-0000

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Frank Musgrove of Hellar Drilling Co., Inc has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: J. M. Stewart

Complete Address: 608 Union Center Bldg., Wichita, Kansas.

Lease Name: Cornwell Well No. # 1

Location: SE NE SE Sec. 17 Twp. 23 Rge. 14 (E)(W) W

County Stafford Total Depth 3929' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cement circulated with 220 sacks. Fill hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving  
Conservation Division Agent