

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-145-20,939-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name ENERGY THREE, INC

Complete Address BOX 1505 GREAT BEND KS 67530

Lease Name REINA Well No. 1

Location C SE - SE Sec. 24 Twp. 21 Rge. 19 (East)(West)

County Pawnee Total Depth 4300 ¹²⁹⁷⁵

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Big Three Oily. Co.

Address Box 52 SAME Gorham Mo 67640 License No. _____

Operation Completed: Hour: 1:45 PM Day: 24 Month: 2 Year: 1982

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows:

8 5/8" S.P. 250' w/ 200 SX common 2% gel - 3% cc.

1st plug @ 230 SX 50/50 Pozmix 4% gel - 3% cc &

1st plug @ 2100' w/ 30 SX (gas zone)

2nd plug @ 1200' w/ 50 SX

3rd plug @ 540' w/ 80 SX

4th plug @ 240' w/ 40 SX

5th Solid Bridge @ 40' → cement 0' w/ 10 SX

7th Rat hole w/ 10 SX 8th Manhole w/ 10 SX cement

Amount of Surface Casing: 250

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Steve Almont
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1982

Signed: _____
Conservation Division Agent

INVOICE
CONSERVATION DIVISION
Wichita, Kansas

3-1-82

DATE 3-2-82

INV. NO. 9525-N