

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-185-17966-0000

RECEIVED
STATE CORPORATION COMMISSION

JUL 22 1966

CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Aspen Drilling Company

Complete Address: P. O. Box 783, Great Bend, Kansas

Lease Name Crissman Well No. # 3

Location NE SW SW Sec. 16 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 4075'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:30PM Day 20th Month July Year 1966

The Above well was plugged as follows:

248' of 8 5/8" surface pipe, cemented with 200 sacks. 4062' of 5 1/2" long string,
cemented with 150 sacks. Plug back T. D. 4030'. Top perforation 3625'. 50 sacks
of cement was pumped on bottom, bringing the top of the cement to 3250'. 2400'
of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid
to 240', rock bridge from 240' to 230'. 10 sacks of cement was mixed in a barr-
el, and put on plug at 230', through the dump bailer, and let set over-night.
Next day hole was bailed dry, and 20 sacks of cement was added to the plug.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with
10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 7/22/66
INV. NO. 3615-W